

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
May 24, 1971

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Mickelson Well No. C-3

Location N/2-SW-NE Sec. 27 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3768'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Ralph Comstock Pipe Pulling, Incorporated,

Address 320 South Park, Stafford, Kansas. License No. 490

Operation Completed: Hour 2:30 PM Day 17 Month 5 Year 1971

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated.  
368 1/2'--5 1/2" Production casing cemented on bottom. Well plugged back to 3500'. Top perforations @ 3472'.

Pushed plug to 3300', sanded back to 3275' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 4 sacks hulls and 5 sacks gel and

followed with 90 Sx. cement from 950' to 650' then 10 Sx. gel from 650' to 250' and

followed with 1 sack hulls from 250' to 200' and finally with 60 Sx. cement from 200'

to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-100#.

(Mudding and cementing operations performed by Allied Cementing Co., Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 3789-11