

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-00592-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Co.  
Complete Address: 617 Union Center, Wichita, Kansas.  
Lease Name Johnson Well No. 1  
Location SE-SE-SE Sec. 4 Twp. 8 Rge. (E) (W) 23  
County Graham Total Depth 3770'  
Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated:   
Plugging Contractor: Ace Pipe Pulling Co.,  
Address: Box # 304, Great Bend, Kansas. License No. 2  
Operation Completed: Hour 5:00P Day 22 Month 3 Year 1963

The Above well was plugged as follows:

280' - 8 5/8" surface pipe cement circulated w/150 Sx. 3768' 5 1/2" cemented with 100 Sx. Well plugged back to 3740'. Top of perforations @ 3706'. Pulled 5 1/2" to 450', circulated heavy gel mud (13 Sx.) and displaced 20 Sx cement thru 5 1/2". Pull casing to 270' and displaced 20 Sx cement thru 5 1/2". Pull casing, set bridge @ 35' and 10 Sx cement to bottom of cellar. (Recovered 2990' 5 1/2" casing).

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 1963

3-27-63

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 3/29/63  
INV. NO. 6483-W

Signed: H. L. Nichols  
Well Plugging Supervisor