

*f* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-20546-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

5-16-72

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Chestnut Well No. 1

Location SW-NE-SW Sec. 4 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3850'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Hellar Drilling Company, Incorporated,

Address 339 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 10:15 AM Day 10 Month 5 Year 1972

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1145' and displaced 110 Cu. Ft. cement  
thru DP from 1145' to 820'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 5-16-72  
INV. NO. 5720-W