

9

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15065-20454-00-00

6-11-71  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Clark Well No. 1

Location CNW-NW Sec. 5 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3470'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 10:00 AM Day 6 Month 6 Year 1971

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru  
DP from 1050' to 725'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from  
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickel  
Well Plugging Supervisor

6-11-71  
3845-W