

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

W

FILE NO. \_\_\_\_\_

LOCATION NW-NE-NE

SEC. 7 TWP. 8 RGE. 23-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Montgomery

Operator Barnett Drilling Co Address First Natl. Bank Bldg. Wichita

Field \_\_\_\_\_ County Graham

Total Depth 4067 Feet.


(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 326 ft. Circulated with cement.  
5 1/2" casing set at 3759 ft & cemented with 200 sacks cement  
Set Plug inside 5 1/2" casing at 3720 ft & 5 sacks cement  
with Mackay Bailor - Shot off & recovered 2820 ft of  
5 1/2" cas - g - Filled with mud to 326 ft. Plug & 15 sacks  
of cement at 326 ft - Surface Plug 25 ft below the  
surface & 10 sacks cement - Filling hole to surface  
Mud between plugs.

Best Self - Pipe Puller

C. H. Stough  
District Conservation Agent

Date 10-9-47



PLUGGING  
WELL SEC 7 T 8 R 23W  
BOOK PAGE 138 LINE 28

X