

81

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Ditting Building
Wichita, Kansas

FILE NO. 117-0

LOCATION NW NW NE

SEC. 8 TWP. 8 RGE. 25

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Montgomery

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Graham

Total Depth 3775 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 100' circulated with cement - 5 1/2" at 3775' with 100 sax
cement behind - Lane Wells plugs to 3750' - top perforations at 3660'.
Chat to 3650', set 4 sax cement with dump bailer - pulled 3020' 5 1/2" -
filled with mud to 160', set rock and 25 sax cement - mud to 55', set rock
and 10 sax cement to bottom cellar.

100
8 8
117
2310
6

7-31-1953

Edward Perry
District Conservation Agent

Date 7-29-53