



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1974  
1-2-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.  
Complete Address Box 352, Russell, Kansas 67665  
Lease Name Ellsworth "B" Well No. 2  
Location C N/2 N/2 SE Sec. 8 Twp. 8 Rge. (E) (W) 23  
County Graham Total Depth 3700'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12:30 P Day 30 Month 12 Year 1974

The above well was plugged as follows:

- Total Depth 3700' 8 5/8 csg set at 170' cwc 150 sk.
- 5 1/2 csg set at 3693' cw 100 sk cmt.
- 5 1/2 csg PBD 3547 1/2' with top perf. (3498)
- Set 5 1/2 wood plug at 1250' -dumped 5 sk cmt W/dump bailer. (1250-1215)
- Cutoff & recovered 1200' of 5 1/2 csg.
- Mixed & pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls -70 sk cmt -
- 15 sk gel & water -released 8 5/8 plug & 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey  
Well Plugging Supervisor

INVOICED

DATE 1/6/75  
INV. NO. 574-W