

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1973
2-7-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas.
Lease Name Montgomery Well No. 3
Location CNE Sec. 8 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3765'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Rockhold Engineering, Incorporated,
Address Box #698, Great Bend, Kansas. License No. 670
Operation Completed: Hour 12:00 M Day 3 Month 2 Year 1973

The above well was plugged as follows:

166'--8 5/8" Surface casing, cement circulated with 125 Sx.
3764'--5 5/8" Production casing cemented on bottom with 150 Sx. Well plugged back to
3741'. Top of perforations @ 3595'.
Pushed plug to 3550' sanded well back from 3550' to 3525' and set 5 Sx. cement with
dump bailer. Pulled 5 1/2" casing (1500') and squeezed well initially with 5 sacks hulls
and and 16 sacks gel and followed with 110 Cu. Ft. cement from 1000' to 675' then 12
sacks gel from 675' to 175' and followed with 30 Cu. Ft. cement from 175' to 100' then
2 sacks gel from 100' to 20' and finally 10 Cu. Ft. cement from 20' to bottom of cellar.
Maximum pump-in pressure-100#. Final shut-in pressure-100#. (Mudding & cmtg. by Allied).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2/7/73
INV. NO. 6951-W