

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1973
2-7-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Montgomery Well No. 2

Location CS/2-S/2-NE Sec. 8 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3739'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 10:30 AM Day 3 Month 2 Year 1973

The above well was plugged as follows:

166'---8 5/8" Surface casing, cement circulated with 125 Sx.
3740'---5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3740'. Top perforations from 3536' to 3540'.
Pushed plug to 3500', sanded back from 3500' to 3460' and set 5 Sx. cement with dump bailer
Pulled 5 1/2" casing, (224') and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 110 Cu. Ft. cement from 950' to 625' then 11 sacks gel from 625' to 175' and followed with 30 Cu. Ft. cement from 175' to 100' then 2 sacks gel from 100' to 20' and finally 10 Cu. Ft. cement from 20' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickala
Well Plugging Supervisor

INVOICED
DATE 2/7/73
INV. NO. 6950-11