

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1964
12-8-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Fender Pipe & Supply, Incorporated.

Complete Address: Box #202, Russell, Kansas.

Lease Name Ellsworth Well No. B-3

Location CSE-NE-SE Sec. 8 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3730

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 2:30PM Day 2 Month 12 Year 1964

The Above well was plugged as follows:

154'--8 5/8" Surface pipe, cement circulated with 115 Sx.
3729'--5 1/2" Production casing, cement with 75 Sx.

Sanded well back to 3720' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" to 569' and circulated heavy gel mud. (used 18 Sx. gel)
Pulled 5 1/2" to 530' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to
150' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @
30' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/8/64
INV. NO. 293-W

Signed: J. P. Roberts
Well Plugging Supervisor