

15-065-61069-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

5/1/64 MAY 1 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name Ellsworth Well No. A-1

Location SE-NW-NE Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3674

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Company, Incorporated,

Address: Box #221, Great Bend, Kansas License No. 49

Operation Completed: Hour 6:00PM Day 25 Month 4 Year 1964

The Above well, was plugged as follows:

1631'--8 5/8" Surface pipe, cement circulated with 110 Sx.
3674'--5 1/2", cemented with 100 Sx. Well plugged back to 3528'. Top per-
forations @ 3423'.

Sanded well back to 3410' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 600' and attempted to circulate heavy gel mud but was unable to
break circulation. Pulled 5 1/2" to 510' and circulated with heavy gel mud,
(used 13 Sx. gel) and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 180'
and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and
10 Sx. cement to bottom of cellar. (Recovered 2500' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/1/64
INV. NO. 9060-W

Signed: N. L. Nichols
Well Plugging Supervisor