

15-065-02467- Form CP-3
KANSAS Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas

1/11/71

Operator's Full Name J. K. Fortner,

Complete Address Box #97, Ellinwood, Kansas.

Lease Name Bethell Well No. 3

Location N/2-S/2-N/2 Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3603'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box # 405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:30 PM Day 8 Month 1 Year 1971

The above well was plugged as follows:

176'--8 5/8" Surface casing, cement circulated with 126 Sx.
3600'--5 1/2" casing cemented on bottom with 125 Sx. Well Plugged back to 3410'. Top perforations @ 3385'.

Squeezed 5 1/2" casing with 25 Sx. cement from 3410' to 3300' and followed with 23 sacks gel from 3300' to 1000' then 50 Sx. cement from 1000' to 600' then 4 sacks gel from 600' to 200' and finally 25 Sx. cement from 200' to surface. Squeezed annulus with initially 5 sacks hulls and 15 sacks gel and finally then 65 Sx. cement from 1000' to 600' then 5 sacks gel from 600' to 200' and finally 25 Sx. cement from 200' to bottom of cellar.

Maximum pump-in pressure on 5 1/2"-300#. FSIP-100#. Max Press. on annulus-200#. FSIP-100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pilels
Well Plugging Supervisor

DATE 1-12-71
INV. NO. 3191-W