

15-065-02975-00 ~~01~~ 01

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

5/1/64

MAY 1 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name Ellsworth Well No. A-2

Location CS  $\frac{1}{2}$ -N  $\frac{1}{2}$ -N  $\frac{1}{2}$  Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3700

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Company,

Address: Box #221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 27 Month 4 Year 1964

The Above well, was plugged as follows:

162' -- 8 5/8" Surface pipe, cement circulated with 115 Sx.  
3700' -- 5 1/2" cemented with 125 Sx. Well plugged back to 3667'. Top per-  
forations @ 3408'.

Sand well back to 3400' and set 5 Sx. cement with dump bailer. Attempted  
to circulate heavy gel mud @ 500', pumped in 6 Sx. gel no circulation.  
pulled 5 1/2" to 400' and circulated heavy gel mud, (used 10 Sx. gel)  
and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 160' and displaced  
20 Sx. ce ment thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and 10 Sx. cement  
to bottom of cellar. (Recovered 620' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 5/1/64  
INV. NO. 9061-w