

15-065-02976-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
1/11/71

Operator's Full Name J. K. Fortner,  
Complete Address Box #97, Ellinwood, Kansas.  
Lease Name Bethell Well No. 21  
Location NW-SE-NE Sec. 17 Twp. 8 Rge. (E) (W)23  
County Graham Total Depth 3622'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling Company, Incorporated,  
Address Box #405, Chase, Kansas. License No. 436  
Operation Completed: Hour 1:15 PM Day 8 Month 1 Year 1971

The above well was plugged as follows:

162'--8 5/8" Surface casing, cement circulated with 120 Sx.  
3620'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back indicated,  
Top perforations @3354'.

Sanded well back to 3300' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing,  
(916') and squeezed well initially with 5 sacks hulls and 17 sacks gel and followed  
with 115 Sx. cement from 1000' to 625' then 11 sacks gel from 625' to 200' and followed  
with 20 Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally  
10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-250#. FSIP-150#.  
(Mudding and Cementing operations performed by Globe Oilwell Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 1-12-71  
INV. NO. 3190-W