

15-065-02977-00-00

KANSAS

Form CP-3
Rev. 6-4-68

Y STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

1/11/71
RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. K. Fortner,

Complete Address Box #97, Ellinwood, Kansas.

Lease Name Bethell Well No. X2 *W/In Rec 10/8/67*

Location NE-SW-NE Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3675'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:30 PM Day 8 Month 1 Year 1971

The above well was plugged as follows:

170'--8 5/8" Surface casing, cement circulated.
3675'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
3450'. Top perforations @ 3394'.

Sanded well back to 3350' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1200') and squeezed well initially with 5 sacks hulls and 17 sacks gel then 115 Sx.
cement from 1000' to 625' then 11 sacks gel from 625' to 200' and followed with 20 Sx.
cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10 Sx. cement
from 30' to bottom of cellar. Maximum pump-in pressure-250#. Final Shut-in pressure-
100#. (Mudding and Cementing by Globe Oilwell Cementing, Inc.,).

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Dickel*
Well Plugging Supervisor

INVOICED
DATE 1-12-71
INV. NO. 3189-W