

15-065-02978-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

1/12/71
RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. K. Fortner,

Complete Address Box #97, Ellinwood, Kansas.

Lease Name Bethell Well No. 4

Location SE-SE-NE Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3602'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 11:30 AM Day 8 Month 1 Year 1971

The above well was plugged as follows:

178'--8 5/8" Surface casing, cement circulated with 135 Sx.
3591'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
3407' Top perforations from 3393' to 3396'.

Sanded well back to 3375' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(893') and squeezed well initially with 5 sacks hulls and 17 sacks gel and followed
with 115 Sx. cement from 1000' to 625' then 11 sacks gel from 625' to 200' and followed
with 20 Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10
Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure 1000#. FSIP-200#.
(Mudding and cementing operations performed by Globe Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1-12-71
INV. NO. 3192-W