

15-065-03096 00-w

CP-3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

2/8/63

FEB 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Co.,

Complete Address: Victoria, Kansas.

Lease Name Ellsworth Well No. 2

Location SW-NW-NW Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3685

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co

Address: Box # 304, Great Bend, Kansas. License No. 2

Operation Completed: Hour 2:30P Day 5 Month 2 Year 1963

The Above well was plugged as follows:

191' 8 5/8" Surface-cement circulated. 5 1/2"-3684' w/1-90Sx Cement

Well plugged back to 3582, top perforations @ 3555'.---Sanded well back  
to 3540', set 4 Sx cement w/dump bailer. Pulled casing to 460' circul-  
ated with heavy mud (20 Sx Gel) and displaced 20 Sx cement. Pulled cas-  
ing to 180', displaced 20 Sx cement. Pulled casing set plug @ 40' &  
10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 2-8-63

WPA NO. 6543-W

Signed: W. L. Nichols  
Well Plugging Supervisor