

15-065-02680-00-01

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

11/2/64
NOV 2 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Higer Well No. A-3

Location SE-NW-NW Sec. 20 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3740

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ace Pipe Pulling Company,

Address: Box #304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00PM Day 26 Month 10 Year 1964

The Above well, was plugged as follows:

151'--8 5/8" Surface pipe, cement circulated with 135 Sx.
3739'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to
3724'. Top perforations @ 3685'.

Sanded well back to 3670' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 500' and attempted to circulate heavy gel mud (5 Sx. gel). Well
would not circulate. Pull 5 1/2" to 440' and displaced 20 Sx. cement thru
5 1/2". Pulled 5 1/2" to 260' and circulated heavy gel mud. (5 Sx. gel) Pulled
5 1/2" to 200' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge
@ 30' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 11/2/64

INV. NO. 83-W