

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8/31/62 AUG 31 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Co
Complete Address: Victoria, Kansas
Lease Name Higer B ^{KCC} _{ZHP} Well No. 1-B
Location SE NE NE Sec. 19 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3740
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ace Pipe Pulling
Address: Great Bend, Kansas License No. 2
Operation Completed: Hour 10AM Day 29 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 182' circulated with cement - 5 1/2" 3739' with 100 sax cement - perf 3684'

Filled with sand to 3670', set 4 sax cement with dump bailer - pulled 2420' 5 1/2" to 500' - pumped mud, hole pressured up - pulled pipe to 450', circulate hole with heavy mud, displaced 20 sax cement through 5 1/2" at 450', heavy mud to 180', displaced 20 sax cement through 5 1/2" - heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Ace Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/31/62
INV. NO. 5624-W

Signed: *Edon Kelly*
Well Plugging Supervisor