

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1964

10/28/64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Brinkmeyer Well No. 1

Location NE-SE-NE Sec. 19 Twp. 8 Rge. (E) (W) 20<sup>23</sup>

County Graham Total Depth 3740'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Company,

Address: Box # 304, Great Bend, Kansas. License No. 2

Operation Completed: Hour 4:00PM Day 23 Month 10 Year 1964

The Above well, was plugged as follows:

192'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
3740'--5 1/2" Production casing cemented with 100 Sx. ~~XXXX~~ Well plugged  
back to 3719'. Top perforations @ 3688.

Sanded well back to 3675' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing to 450' and circulated heavy gel mud (12 sacks),

Displaced 20 Sx. cement thru 5 1/2" casing @ 450'. Pulled 5 1/2" to 180'

and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @

35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 10/28/64

INV. NO. 53-W