

15-065-02328-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NW NW SW
SEC. 20 TWP. 8 RGE. 23W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Kobler

Operator Imperial Oil of Kansas, Inc. Address 903 W. North Blvd. Wichita, Kans

Field _____ County Graham

Total Depth 3774 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 189' Circulated with cement - 5 1/2" at 3774 - with 100

sax cement behind - P.B. to 3728', perforated 3/12'

Filled with sand to 3700', set 4 sax cement with dump bailer,

pulled 3100' 5 1/2" - filled hole with heavy mud to 180', set rock

and 20 sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

District Conservation Agent

4-6-57

Date _____

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1957

CONSERVATION DIVISION
WICHITA, KANSAS

4/8/57

PLUGGING
FILE SEC. 20 T. 8 R. 23W
BOOK PAGE 4 LINE 37