

15-068-02980-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11/3/64
NOV 3 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Higer Well No. A-2

Location SW-NW-NW Sec. 20 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3730

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company,

Address: Box #304, Great Bend, Kansas. License No. 2

Operation Completed: Hour 1:30PM Day 27 Month 10 Year 1964

The Above well, was plugged as follows:

199'--8 5/8" Surface pipe, cement circulated with 120 Sx.
3729'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to 3719'. Top perforations @ 3440. Well cemented thru 2-stage tool from 1922' to surface.
Squeezed well with 18 Sx. gel from 3719 to 640', 10 Sx. cement from 640' to 560', 2 Sx. gel from 560' to 320' and 40 Sx. cement from 320' to bottom of cellar. Final shut in pressure 100#.

(No attempt to recover casing)

I hereby certify that the above well was plugged as herein stated.

DATE 11/3/64
INV. NO. 104-U

Signed: [Signature]
Well Plugging Supervisor