

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-065-20702-00-00

Form CP-3
Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

9-30-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address P. O. Box #370, Hays, Kansas.

Lease Name Griffith Well No. A-1

Location SE-SE-SW Sec. 21 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 4:15 PM Day 23 Month 9 Year 1974

The above well was plugged as follows:

167'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 110 Cu. Ft. cement
thru DP from 1025' to 700'. Pulled DP to 180' and displaced 30 Cu. Ft. cement thru
DP from 180' to 105'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/11/74
INV. NO. 10,000-W