

15-065-19075-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11/3/64
NOV 3 1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,
Complete Address: Victoria, Kansas.
Lease Name Higer Well No. A-1
Location SW-SW-NW Sec. 20 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3760'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ace Pipe Pulling Company
Address: Box # 304, Great Bend, Kansas. License No. 2
Operation Completed: Hour 5:30PM Day 28 Month 10 Year 1964

The Above well, was plugged as follows:

185'--8 5/8" Surface pipe, cement circulated with 120 Sx.
3755'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to
3745'. Top perforations @ 3696.

Sand well back to 3685 and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 500' and attempted to circulate heavy gel mud, Pumped in 3 Sx.
gel. Pulled 5 1/2" to 450' and circulated heavy gel mud (5 Sx. gel) and
displaced 20 Sx. cement @ 450'. Pulled 5 1/2" to 180' and displaced 20
Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

11/3/64
105-W