

DISTRICT CONSERVATION AGENT'S REPORT

15-065-02436-00-00

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 146-20

LOCATION NE NE SW

SEC. 21 TWP. 8 RGE. 23

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Mc Coy

Operator Sunray Oil Corp Address Box 195 Great Bend, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3795 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 329' circulated with cement - 5 1/2" at 3794' with

50 sax cement behind - top perforations at 3583'.

Filled with sand to 3560', set 5 sax cement with dump bailer,

pulled 3380' 5 1/2", filled hole with mud to 320', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 21 T 8 R 23W  
BOOK PAGE 146 LINE 20

*J. Edgar Perry*  
District Conservation Agent

Date 4-6-52

4-10-52