

DISTRICT CONSERVATION AGENT'S REPORT

15-065-19078-06-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 21 TWP. 8 RGE. 23

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Legere

Operator Peel-Hardman Address Hoisington, Kans

Field _____ County Graham

Total Depth 4080 Feet.

Plugging Contractor Bert Self

Plugging Contractor's License No. 48

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 270' circulated with cement - 5 1/2" at 3825' with

150 sax cement behind - Lane Wells plugs to 3725' - perforated

at 3704'.

Filled with chat to 3690', set 4 sax cement with dump bailer,

pulled 2400' 5 1/2" - filled with mud to 270', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

District Conservation Agent

Date 2-28-55

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1955

CONSERVATION DIVISION
Wichita, Kansas

2-28-55

PLUGGING
FILE SEC 21 T 8 R 23W
BOOK PAGE 79 LINE 2