

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20438-0000

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1971

CONSERVATION DIVISION
Wichita, Kansas

5-17-71

Operator's Full Name Re'al Petroleum Company,

Complete Address 6810 West Kellog, Wichita, Kansas. 67209

Lease Name Virgil Kemp Well No. 1-B

Location SE-NW-NE Sec. 22 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address 300 West Douglas, Wichita, Kans. License No.

Operation Completed: Hour 1:30 AM Day 14 Month 5 Year 1971

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru
DP from 1075' to 750'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/17/71

INV. NO. 3707-W