

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 32 TWP. 8S RGE. 21W E/W
Location as in quarters or footage from lines:
SE SE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Arrowhead Petroleum Company, Inc.
Lease Name Green #2 Well No. _____
Office Address Suite 29 400 N. Woodlawn Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5-20-82
Plugging completed 5-21-82
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom _____ T.D. 3774'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	217'	none
				4-1/2"	3772'	3018'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed bottom plug to 3400', ran 50' of sand and 4 sacks cement. Shot casing @3020' and pulled a total of 75 joints of 4-1/2" casing. Plugged well with 4 sacks hulls, 17 sacks gel, 1 sack hulls, 70 sacks cement, 8 sacks gel, 8-5/8" plug, 70 sacks cement.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1982
May 25 1982
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1982

My Commission expires: _____



Irene Hoover
Notary Public.