

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Graham

County. Sec. 23 Twp. 8 Rge. (E) 21 (W)

Location as "NE<sup>1</sup>/<sub>4</sub>NW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines SW/4

Lease Owner Phillips Petroleum Company

Lease Name Jelie Well No. One

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 10, 1945 19

Application for plugging filed By Phone - February 11, 1945 19

Application for plugging approved By Phone - February 11, 1945 19

Plugging commenced February 11, 1945 19

Plugging completed February 11, 1945 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. Kerr

Producing formation None Depth to top Bottom Total Depth of Well 3813 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing Kansas City	Dry	3363'	3576'	13 3/8"	184'	None
Arbuckle	Dry	3775'	3813'			

FEB 16 1945

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 3813' to 190', ran wood plug at 190' with 20 sacks of cement. Filled with mud to 20', ran wood plug at 20' with 10 sacks of cement in filling to base of cellar. Note: Halliburton pump truck used in plugging operation.

PLUGGING  
FILE 23 8 21 W  
BOOK 45

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ralph McKnight  
Address Box 528 - Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Ralph McKnight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph McKnight Dist. Supt.

Box 528 - Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1945

My commission expires June 14, 1948  
Robert T. Mason Notary Public.

# Formation Record

*slate*

Lease **JELIE**

Well No. **ONE**

FROM	TO	Formation	REMARKS
0	345	Shale and Shells	<u>Derrick Floor Elevation 2191'</u>
345	435	Shale	
435	678	Shale and Shells	
678	765	Sand	
765	1154	Shale and Shells	
1154	1185	Iron Pyrite	
1185	1191	Chalk	
1191	1208	shale	
1208	1474	Sand	
1474	1485	Sand and Shale	
1485	1608	Shale and Red Bed	
1608	1698	Red Bed	
1698	1795	Anhydrite	Top of Anhydrite 1703'.
1795	1868	Anhydrite and Shale	
1868	1958	Shale	
1958	2172	Shale and Shells	
2172	2508	Lime and Shale	
2508	2548	Lime	
2548	2673	Lime and Shale	
2673	2755	Lime	
2755	3068	Lime and Shale	
3068	3126	Shale	
3126	3208	Lime and Shale	
3208	3225	Lime	
3225	3274	Lime and Shale	
3274	3608	Lime	Top of LKG 3563' with no shows. Base of LKG 3576'.
3608	3678	Lime and Shale	
3678	3737	Conglomerate	
3737	3744	Lime	
3744	3785	Lime and Shale	Top of Arbuckle 3775'. Had porosity but no saturation.
3785	3815	Lime	

*Feb 16/1945*

PLACING

FILE 23 8-21W  
BOOK 4 45