

15-065-00115-00-51

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 33 Twp. 8 Rge. 21 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines. C SE NW SW
Lease Owner Morrison Producing Company
Lease Name Koehn1 Well No. 1
Office Address El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8-31-65 19
Plugging completed 9-1-65 19
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3680 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	190'	None
				5-1/2"	3680'	2619'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug back @ 3435', sanded to 3385' and dumped 5 sacks of cement @ 3385' with dump bailer. Pulled 5 1/2" casing to 600' and circulated pipe with 20 sacks of gel mud. Pulled 5 1/2" casing to 540' and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 200' and pumped in 25 sacks of cement. Pulled pipe to 35' and ran 15 sacks of cement. Pulled balance of 5 1/2" casing and capped well with 2 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1965

CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1965

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

COMMENCED:
COMPLETED:

Morrison Producing Company
LEBEN DRILLING, INC.
KOEHNLE #1 Washdown
SE NW SW Sec. 33-8S-21W
GRAHAM COUNTY, KANSAS
8-13-65
8-15-65

0

3684
3684'

Washed Down
RTD - Set 5 1/2" Casing


I, Leslie Kite, do hereby certify that the above and fore-
going is a true and correct copy of the log of the Koehnle
#1 Washdown well, located SE NW SW of Section 33, Township
8 South, Range 21 West, Graham County, Kansas, as reflected
by the files of Leben Drilling, Inc.



Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public,
in and for Barton County, Kansas, this 19th day of August,
1965.



Ulanda Nichols

My Commission Expires: April 1, 1967

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1965
Sep 8, 1965
CONSERVATION DIVISION
Wichita, Kansas