


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 1 Twp. 8S Rge. (E) 22 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW

Lease Owner Harry Gore - Veeder Supply Company

Lease Name Gordon Well No. 1

Office Address 400 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 28, 1952

Application for plugging filed March 28, 1952

Application for plugging approved March 28, 1952

Plugging commenced March 28, 1952

Plugging completed March 28, 1952

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	182'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3800' to 170'. Set plug

with 15 sacks cement and 1/2 sack of cotton seed hulls.

Filled hole with heavy mud to 40'. Set plug with 10 sacks

of cement and 1/2 sack of cotton seed hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Veeder Supply & Development Co.

Address P. O. Box 201

Cherryvale, Kansas

APR 8 1952

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.

FLOYD W. HILD

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT COMPANY

(Signature) Floyd W. Hild

Box 201, Cherryvale, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 1952.

Gleo Lawson

Notary Public.

My commission expires July 11, 1952

PLUGGING
FILE SEC 1 T 8 R 22
BOOK PAGE 5 LINE 30

15-065-00366-00-00

Company Harry Gore - Veeder Supply Co.

Sec. 1 T. 8 R. 22

Loc. NW NW NW

County Graham County, Kansas

Farm Gordon

No. 1

Total Depth 3800'

Comm. 3-17-52

Comp. 3-28-52

Shot or Treated


Contractor Veeder Supply Co.

Drilled with Rig - D

Issued

No. of Days - 12

No. of Bits -



20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Casing

Elevation

Surface hole drilled and 182 feet casing set when rotary moved in.

Production

Figures Indicate Bottom of Formation

Surface Hole	0	182	182
Shale	182	330	148
Shale Shells	330	585	255
Shale	585	800	215
Sand Shale Shells	800	890	90
Sand Shale	890	960	70
Sand Shells	960	1275	315
Sand	1275	1300	25
Sand Shale	1300	1420	120
Red Bed	1420	1720	300
Anhydrite	1720	1755	35
Shale Shells	1755	2215	460
Line Shale	2215	2815	600
Shale Shells	2815	2985	170
Shale Lime	2985	3215	230
Lime	3215	3685	470
Shale Lime Cherty	3685	3700	15
Conglomerate	3700	3743	43
Chert	3743	3785	42
Lime Arb.	3785	3800	15
Total Depth	3800'		

Plugged at 170 feet with 15 sacks cement.
Plugged at 40 feet with 10 sacks cement.

PLUGGING
 FILE SEC 1 T. 8 R. 22
 BOOK PAGE 5 LINE 30

APR 8th 1952