

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-20, 444-00-00

LEASE NAME Buckner

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR H-30, Inc.

SEC. 1 TWP. 8S RGE. 22 (N) or (W)

ADDRESS 251 N. Water, Suite 10; Wichita, KS 67202

COUNTY Graham

PHONE#(316) 263-2043 OPERATORS LICENSE NO. 5107

Date Well Completed \_\_\_\_\_

Character of Well Abandoned producer

Plugging Commenced 10-16-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-16-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3600' Bottom 3662' T.D. 3670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From surface	To	Size	Put in	Pulled out
		surface	207	8-5/8"	4/29/71	N/A
		surface	3661	5-1/2"	4/29/71	N/A

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Squeezed down 5-1/2" casing at 500# maximum pressure - mixed hulls with 175 sacks cement, 20 sacks of gel and shut in.

Squeezed down annulus (8-5/8" casing) at 900# maximum pressure, mixed hulls with 150 sacks cement, 6 sacks gel and shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor N/A License No. N/A

Address N/A

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Dean Britting

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 85

Teresa Quinton  
 Notary Public

My Commission Expires: 10-14-87



STATE CORPORATION COMMISSION  
 JAN 31 1986 Form CP-4  
 JAN 3 1986 Revised 08-84

15-065-20444-00-00

**ALLIED CEMENTING COMPANY, INC.**

TELEPHONE:  
AREA CODE 913 483-2627

P. O. BOX 31  
RUSSELL, KANSAS 67665

15-065-20,444

TO: H-30 Drilling Inc.  
251 N. W ter Suite 10  
Wichita, Kansas 67202

INVOICE NO. 44657  
PURCHASE ORDER NO. 16  
LEASE NAME Buckner #1  
DATE Oct. 24, 1985

SERVICE AND MATERIALS AS FOLLOWS:

Common 195 sks @\$5.00	\$ 975.00	
Pozmix 130 sks. @\$2.10	273.00	
Gel 46 sks @\$7.25	333.50	
Hulls 10 sks. @\$14.00	<u>140.00</u>	yes
		\$ 1,721.50
Handling 381 sks @\$0.90	342.90	
Mileage @\$0.66 per ton mi. (29)	<u>36</u> 322.32	2662
Plugging	340.00	
Mi @\$1.00 pmp. trk.	<u>29.00</u>	
		1,034.22
		<u>36.20</u>
		Total \$ 2,791.92

*Plugging Cement*

*AMC  
11/11/85  
11/11/85*

207 8 5/8" 4/29/71  
3661 5 1/2" 4/29/71

RECEIVED RECEIVED  
STATE CORPORATION COMMISSION  
THANK YOU  
JAN 3 1986  
JAN 3 1986  
CONSERVATION DIVISION

OCT 25 1985

279.19  
2512.73

15-065-20444-00-00

913-483-2627, Russell, Kansas  
316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812  
Phone Kiowa 316-825-4618

old

# ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

N<sup>o</sup> 1103

Date	10-16-85	Sec.	1	Twp.	8 <sup>s</sup>	Range	22 <sup>w</sup>	Called Out	7:30 A.M.	On Location	10:00 A.M.	Job Start	10:30 A.M.	Finish	12:15 P.M.	
Lease	Buckner	Well No.	1	Location				18 <sup>s</sup> 24 JCT 1/2 W 3/4 N W side	County	Graham	State	Ks.				

Contractor		Owner	
Type Job	D & A	Same	
Hole Size	7 7/8"	T.D.	3670'
Csg. Size	5 1/2"	Depth	3665'
Csg. Size	8 5/8"	Depth	207'
Drill Pipe		Depth	
Tool		Depth	
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf.			1985

Charge To	H-30 Drilling, Inc.
Street	251 N. Water, Suite 10
City	Wichita
State	Ks. 67202
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X	

EQUIPMENT		
Pumptrk	No	Cementer
	191	Helper
		Gary H.
		Dave P.
Pumptrk	No	Cementer
		Helper
Bulktrk	#	Driver
	116	Marlin H.
Bulktrk		Driver

CEMENT	
Amount Ordered	325 sks 60/40 poz 620 gel
Consisting of	26 sks gel & 10 sks hulls
Common	195 sks @ 5.00/sk. 975.00
Poz. Mix	130 sks @ 2.10/sk. 273.00
Gel.	46 sks @ 7.25/sk. 333.50
Chloride	
Quickset	
Hulls	10 sks @ 14.00/sk. 140.00

DEPTH of Job	
Reference:	#10 Pumptruck - plug well 1st 340.00
	#14 mileage @ 1.00/mi. 29.00
	Sub Total 369.00
	Tax
	Total

Sales Tax	
Handling	@ 90¢/sk. (381 sks) 342.90
Mileage	@ 66¢/ton mi. (29 mi) 322.32
Sub Total	2386.72
Total	

Remarks: Down 5 1/2" csg., at 500 # max. pressure, mixed hulls: w/25 sks cement, 10 sks gel, 25 sks cement, 10 sks gel, & 125 sks cement & shut in.  
Down annulus (8 5/8" csg.); at 900 # max. pressure, mixed hulls: w/50 sks cement, 6 sks gel, 100 sks cement, & shut in.

JAN 3 1986  
JAN 3 1986  
CONSERVATION DIVISION  
Wichita, Kansas

STATE CORPORATION COMMISSION