


15-065-21230-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 3 Twp. 8S Rge. 22W ~~EW~~
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
SE NW SE ~~NE~~
Lease Owner Zenith Drilling Corporation, Inc.
Lease Name SWITZER Well No. 1
Office Address 505 Fourth Financial Center, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed May 11 19 80
Application for plugging filed (Verbally) May 11 19 80
Application for plugging approved (Verbally) May 11 19 80
Plugging commenced May 11 19 80
Plugging completed May 11 19 80
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3610'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3610'
Set 1st plug at 890' with 70 sacks,
2nd plug at 200' with 20 sacks,
3rd plug 40' solid bridge with 10 sacks,
and rathole with 5 sacks.

Plug was down at 11:00 p.m., 5-11-80.

RECEIVED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. 6-5-80
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1980

My commission expires _____



Sherrie L. Brooks
Notary Public.

CONTRACTOR'S WELL LOG

15-065-21230-00-00

OPERATOR: Zenith Drilling Corporation, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SWITZER #1E
 LOCATION: SE NW SE, Section 3-8S-22W
 Graham County, Kansas
 SPUD DATE: 5-6-80
 COMPLETION DATE: 5-11-80

0	195	Sand & Clay
195	210	Shale
210	1733	Shale & Sand
1733	1765	Anhydrite
1765	2169	Shale
2169	2407	Shale & Lime
2407	3009	Shale
3009	3224	Shale & Lime
3224	3400	Shale
3400	3430	Lime & Shale
3430	3550	Lime
3550	3560	Shale & Lime
3560	3610	Lime
	3610	Rotary Total Depth

Spud hole at 1:00 p.m., 5-6-80. Drilled 210' of 12 1/4" hole. Ran 5 joints of 8-5/8" - 20# casing. (Tally 200'). Set at 207' R.T.D. Cemented with 160 sacks of common, 3% Ca.Cl., 2% gel. Cement did circ. Plug was down at 4:30 p.m., 5-6-80. Drilled out from under surface 2:30 a.m., 5-7-80.

T.D. 3160'. Set 1st plug at 890' with 70 sacks, 2nd plug at 200' with 20 sacks, 3rd plug 40' solid bridge with 10 sacks, and rathole with 5 sacks. Job was complete at 11:00 p.m., 5-11-80.

SAMPLE TOPS:

Anhydrite 1733'(+ 409)
 B/Anhydrite 1755'(+ 387)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
 JUN 5 1980

6-5-80

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SWITZER #1, SE NW SE, Section 3-8S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 2nd day of June, 1980.

Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public

