

15-065-01075-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham

County. Sec. 4 Twp. 8S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NE

Lease Owner Imperial Oil Company

Lease Name HARRISON Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-9-64 19

Application for plugging filed 7-9-64 19

Application for plugging approved 7-9-64 19

Plugging commenced 7-9-64 19

Plugging completed 7-9-64 19

Reason for abandonment of well or producing formation No
commercial quantities of oil found.

If a producing well is abandoned, date of last production 0 0 --- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3653 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	Casing:	8-5/8"	205'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 750' with 20 sacks cement;

Set second plug at 200' with 20 sacks cement;

Set third plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Imperial Oil of Kansas, Inc. (If additional description is necessary, use BACK of this sheet)
Address Box 784, Great Bend, Kansas 7-27-64

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Raymond R. Dombaugh

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Raymond R. Dombaugh
780 Fourth National Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of July, 19 64

My commission expires July 5, 1966

Bette J. Silcott
Bette J. Silcott, Notary Public.

15-065-01075-00-00

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Bldg.
Wichita, Kansas

HARRISON NO. 1
C SE NE, Sec.4-8S-22W
Graham County, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

7-27-64

CONSERVATION DIVISION
Wichita, Kansas

Total Depth: 3653 ft.
Elevation: 2181 KB
Commenced: July 2, 1964
Contractor: Imperial Oil of Kansas, Inc.
Rig #1
Casing Record: Set 205 ft. of 8-5/8" surface pipe with 175 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>
Sand & Shale	205'	
Shale	580'	Anhydrite --
Shale & Sand	1340'	Heebner 3397 (-1216)
Dakota Sand	1540'	Toronto 3421 (-1240)
Shale-Red Bed	1810'	Lansing 3436 (-1255)
Anhydrite	1841'	Base Kansas City 3634 (-1453)
Shale & Red Bed	1970'	
Shale & Lime	2635'	Rotary Total Depth: 3653 (-1472)
Shale	2750'	
Lime & Shale	3448'	
Lime & Chert	3495'	
Lime & Shale	3515'	
Lime	3653'	

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 22nd day of July, 1964.

My commission expires: July 5, 1966

Bette J. Silcott
Bette J. Silcott, Notary Public