

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Graham County, Sec. 5 Twp. 8S Rge. 22 (E) (W) X

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Rocket Schusterman Oil Account  
Lease Name Sanford Well No. 2  
Office Address 1209 Mid Continent Building Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 10-22-69 19\_\_\_\_  
Application for plugging approved 10-23-69 19\_\_\_\_  
Plugging commenced 12-29-69 19\_\_\_\_  
Plugging completed 1-10-70 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3792 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	223	None
				5 1/2	None	834' .40

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Starting to dig cellar.  
Moved unit into location.  
Rigged up unit. Sanded to 3525' and dumped 5 sacks of cement. Rigged up jacks, had 8" stretch on 2,500 psi. Shot pipe at 2400' - 2000' - 1800' - 1700' - 1400' - 1000' and 800'. Pulled 25 joints of casing.  
Finished pulling 10 joints of casing. Tore down unit.  
Allied Cementing squeezed well with 5 sacks of hulls, 35 sacks of mud and 135 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 6 1970  
FEB 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)

Subscribed and sworn to before me this 30 day of January, 19 70



Notary Public.

DRILLER'S LOG

Company: Anderson-Prichard Oil Corporation

SW NE NW  
Sec. 5, Twp. 8S, Rge. 22W,

Farm Name: Sanford Well No. 2

County: Graham,  
Kansas

Total Depth: 3792'  
Comm: 6-13-53 Comp: 6-25-53

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1969 Elevation:

Contractor: Glenn W. Peel

CONSERVATION DIVISION  
Wichita, Kansas

Casing: 8 5/8" 223' cem.  
5 1/2" 3791' cem.

OCT 23, 1969

Figures below indicate bottom of formations:

Surface Clay and Sand	0 -	225
Shale		1050
Sand and Shale		1765
Shale		1770
Anhydrite		1805
Shale		2335
Lime		2405
Shale and Lime		3030
Lime		3792
Total Depth		3792

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Way Herber

SUBSCRIBED AND SWORN to before me this 2nd day of July, 1953.

My Commission expires June 4, 1955

Marion M. Whit  
Notary Public