

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 065-22428-00  
 LEASE NAME CHAIFANT

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1  
2310 Ft. from S Section Line

1320 Ft. from E Section Line  
 SEC. 5 TWP. 8S RGE. 22 (E) or (W)

LEASE OPERATOR Burch Exploration INC.

ADDRESS 11225 Edinborough Way Parker, Colo. 80134

PHONE # (303) 841-9417 OPERATORS LICENSE NO. 7448

Character of Well D&A

COUNTY GRAHAM  
 Date Well Completed 1-6-1988

Plugging Commenced 1-6-1988

Plugging Completed 1-6-1988

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? YES If not, is well log attached? YES

Producing Formation LANSING K.C. Depth to Top 3397' Bottom 3597' T.D. 3650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>SAND</u>	<u>0</u>	<u>318</u>	<u>8-5/8</u>	<u>NEW</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 3650 feet each set.

RUN DRILL PIPE TO 1350' AND 100 BBL H<sub>2</sub>O SPACER. MIX 25 SKS 60/40 POZ MIX 670 GEL. RUN 3 1/2 BBL SPACER. DISPLACE WITH BALANCE. PULL DRILL PIPE TO 1150'. 100 BBL H<sub>2</sub>O SPACER. MIX 100 SKS 60/40 POZ. 670 GEL. WITH 1 SK. OF HIGH SDF. 3 1/2 BBL S. OF BALANCE. PULL DRILL PIPE TO 375'. MIX 10 SKS 60/40 POZ MIX 670 GEL. PUSH PLUG TO HO. FILL TO SURFACE. PLUG MUDS HOLD STRAIGHT TO SURFACE. JOB COMPLETE.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GOLDEN EAGLE DYLE INC. License No. 8682

Address PO BOX 983 MUDOK, NE 69001

STATE OF NEBRASKA COUNTY OF Red Willow, ss.

Melvin L. Taylor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. David Burch

(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of March, 19 88

RECEIVED  
 STATE CORPORATION COMMISSION

Notary Public

My Commission Expires: 11-13-90

MAR 11 1988  
 mar 11, 1988  
 CONSERVATION DIVISION  
 Wichita, Kansas

Form CP-4  
 Revised 08-84