

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20210-00-00

Spot: NESWSW

Sec/Twnshp/Rge: 8-9S-19W

990 feet from S Section Line,

990 feet from W Section Line

Lease Name: BAYARD

Well #: 2

County: ROOKS

Total Vertical Depth: 3553 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3548	0	w/150 sxs cmt
SURF	8.625	207	0	w/150 sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/01/2008 11:00 AM

Plug Co. License No.: 3152

Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: DALE POE

Company: POE SERVICING INC

Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel spacer.
Fluid at surface. No squeeze records.
Perforate at 1925' - 1525' - 825'.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/01/2008 3:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated two shots per foot at 1925' - 1525' - 825'. PBTD 3423'.
Ran tubing to 3400' - pumped 11 sxs gel spacer - followed with 40 sxs cement with 200# hulls.
Pulled to 1950' - pumped 200 sxs cement with 300# hulls cwc.
PTOH. Squeezed 5 1/2" casing with 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Hooked up to backside - pumped 20 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#. Blew hole in 8 5/8" below head.

Perfs:

Top	Bot	Thru	Comments
3423	3425		
3406	3403		
3403	3406		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 08 2008

CONSERVATION DIVISION
WICHITA, KS

FEB 06 2008

KATHOL PETROLEUM, INC.
WICHITA, KS.

#2 BAYARD

8-9-19W
NE SW SW

Contr. CO. TOOLS

Cty. ROOKS

Geol. FROSTY COX

Pool MC CLELLAN

E. 2064 KB Cm. 5/8/69

Cp. 8/7/69 IP PMP 41 BOPD + 7
BWPD/LANS 3403-06

API 15-163-20,210

LOG Tops	Depth	Datum	Csg.
HEEB	3231	-1167	8" 207/150 sx; 5 1/2" 3548/150
TOR	3254	-1190	DST 3392-3420/1', 400' MUD, PRESS NOT RECORDED
LANS	3271	-1207	DST 3417-35/2', 120' MUD, 120' O&GCM, 20% OIL, 120' HO&
BKC	3476	-1412	GCM, PRESS NOT RECORDED
CONG	3528	-1464	DST 3390-3435/2', 120' GIP, 185' O&GCM, 60' HO&GCM,
ARB	3545	-1481	120' FROGGY OIL, BHP 304- 304#/30", FP 80-200#
LTD	3553	-1489	PF 3437-41, 500 MA, 2000 REG ACID, PF 3423-25, COMM, SET PLUG, /3403-06, 1500 ACID, SWB LD, FU 1100' FL/2 DAYS, SWB 13 BFPH, 10%W, PULLED PLUG, POP PMP 41 BO & 7 BW NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS