

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21330-00-00
Spot: NESWSE Sec/Twnshp/Rge: 33-8S-25W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BLAIR Well #: 2
County: GRAHAM Total Vertical Depth: 4095 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4088	0	w/150 sxs cmt
SURF	8.625	252	0	w/160 sxs cmt

133.09

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2008 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOE ABEL Company: DNR OIL AND GAS, INC. Phone: (303) 825-8956

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2008 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 252' w/160 sxs cement.
4 1/2" production casing set at 4088' w/150 sxs cement.
PBTD with bridge plug at 3980'. Cement squeezed at 3818' - 3822'.
Perforated production casing at 1425' and 2250'.
Ran tubing to 2500' - pumped 200 sxs cement with 700# hulls.
Pulled tubing to 1200' - pumped 225 sxs cement with 250# hulls - cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 30 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 45 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Operator elected to use all cement due to poor casing condition.

Perfs:

Top	Bot	Thru	Comments
3998	4002		
3951	3953		
3858	3860		
3822	3818		
3821	3822		

INVOICED
DATE 2-14-08
INV. NO. 2008001206

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 08 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENT COMPANY-TICKET #167

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

Form CP-2/3

FEB 04 2008

MILES PETROLEUM INC. & JOHN ROY EVANS
 BOX 385
 CLAFLIN, KS 67525
 #2 BLAIR
 33-8-25W
 NE SW SE

CONTR HELBERG DRILLING CTY GRAHAM
 GEOL LARRY BOOKLESS FIELD KNOLL NE

E 2539 KB CM 12/3/80 CARD ISSUED 4/30/81 P 40 80 & 20 BWPD
 2534 GL 15-065-21,330 LANS 3850-3865

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		2224	+ 315
TARK LM		3140	- 601
HOW		3507	- 968
TOP		3568	-1029
HEEB		3780	-1241
TOR		3803	-1264
LANS		3817	-1278
RTD		4095	-1556

8 5/8" 259; 4 1/2" 4095

DST (1) 3810-90/30-45-60-45, 300' o,
 GIP, REC 420' GSY MDY OIL (20% W,
 60% o), SIP 1075-1053#, FP 86-
 108/162-216#

DST (2) 3928-85/30-30-30-30, 10' o
 SPKD M, SIP 806-645#, FP 64-64/
 64-64#

DST (3) 3980-4025/30-30-30-30, 10' M,
 SIP 646-603#, FP 54-54/65-65#

MICT - CO, FP (LWR KC) EST 3950-55;
 3975-80, 3995-4000, SWB DWN & REC SO &
 WTR, SET PLUG, PF (U LANS) EST 3850-65
 AC 2000G, SWB LD W/SO, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS