

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20240-00-02
Spot: S2S2SW Sec/Twnshp/Rge: 2-8S-23W
330 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: MONTGOMERY Well Number: 3
County: GRAHAM Total Vertical Depth: 3756 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: PO BOX 70 234 W. 11TH. STE A
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3755 w/200 sxs cmt
Surface Casing Size: 8.625 feet: 247 w/175 sxs cmt

#122⁰⁷

Well Type: EOR UIC Docket No: E19121.1 Date/Time to Plug: 09/15/2003 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 10% gel - 600# hulls.
DV at 1928' w/425 sxs.
Perfs 3547' - 3704' OA. Fluid at 1250'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/15/2003 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing Company tied onto 5 1/2" casing - pumped 285 sxs 60/40 pozmix - 10% gel with 600# hulls.
Max. P.S.I. 1200#. S.I.P. 600#.
Tied onto backside and pressured to Max. P.S.I. 300#.
Blew a small hole in top of casing. No S.I.P.

RECEIVED
9-17-2003
SEP 17 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14178.

Plugged through: CSG

District: 04

110-

Signed

Patricia Staab

(TECHNICIAN)

INVOICED

DATE

9-17-03

INV. NO.

2004060517

Form CP-2/3 ✓

SEP 15 2003

THE MAURICE L. BROWN CO.
1500 VICKERS-KSB&T BLDG.

#3 MONTGOMERY


2-8-23W
S/2 S/2 SW

WICHITA, KS.

CONTR ABERCROMBIE DRLG., INC. CTY GRAHAM

GEOL _____ FIELD FABRICIUS SOUTH

E 2243 KB CM 5/4/77 CARD ISSUED 8/18/77 IP SWDW
LKC 3545-3704 OA



API 15-065-20,240-A

LOG	TOPS	DEPTH	DATUM
ANH	1895	+ 348	
HEEB	3474	-1231	
TOR	3500	-1257	
LKC	3517	-1274	
BKC	3720	-1477	
LTD	3726	-1483	
RTD	3730	-1487	
DDTD	3756	-1513	

OLD INFO: OPERATOR WAS HERNDON DRLG.
 CO. #1 PEMBLETON; SPD 7/3/69, SET 8-
 5/8" 247/175SX; COMPLETED AS D&A/PENN.
 7/17/69
 DST (1) 3535-57/30", 5' M W/F SP 3, SIP
 597-335#/30", FP 15-22#
 DST (2) 3573-95/11', 165' MSW, SIP 1234-
 1121#/30", FP 8-90#
 DST (3) 3673-93/90", 65' BLK OIL GR
 21", 60' HOCM, SIP 880#/30"-200#/
 30", FP 22-60#
 NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

THE MAURICE L. BROWN CO.

#3 MONTGOMERY

2-8-23W
S/2 S/2 SW

NEW INFO: WSH DWN 3756', SET 5 1/2" 3755/675SX, MICT - PF 3703-
 U4, 368T-83, AC 1500, W/BALL SEALERS, SWB LD, AC 6000, SWB
 1.67 BOPH/3 HRS, PF 3545-48, RBP @ 3600, AC 500, SWB LD, AC
 500 - 28% + 1500 SS-20, SWB LD, PULL RBP, SWB 1.67 BOPH/4 HRS
 45% OIL, SWDW