

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21940-00-02 *01 KCCapB*
Spot: W2SESWNW Sec/Twnshp/Rge: 26-29S-4E
2821 feet from S Section Line, 4569 feet from E Section Line
Lease Name: EB SHAWVER II Well #: 4-26
County: BUTLER Total Vertical Depth: 2937 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2937		100 SX
SURF	8.625	248		150 SX

#95.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2007 12:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROBBIE WILLIAMS Company: STELBAR OIL CORPORATION, INC Phone: (316) 641-0024

Proposed Plugging Method: PER KCC INSTRUCTIONS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/16/2007 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-12-2007, SET CIBP @ 2795', DUMP BAILED 5 SXS CEMENT ON TOP, SHOT 5-1/2" CASING @ 1400', 4-13-2007, LAYED DOWN 36 JTS (1400') 5-1/2" CASING 4-16-2007, RIH W/TBG @ 300', CONSOLIDATED CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 108 SXS 60/40 POZMIX 4% GEL TO SURFACE, P.A. COMPLETE 1000 04-16-2007. CEMENT CIRCULATED TO SURFACE. CONSOLIDATED CEMENT TICKET #17175.

Perfs:

Top	Bot	Thru	Comments
2853	2857		
2836	2842		

INVOICED
DATE 7-2-07
INV. NO. 2008060023

Remarks: -096.96890,37.49795, PERFS 2836"-2857", PBTD 2916'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

PKT