

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER NONE 15-019-19482-00-00  
SW NE SW Sec/Twp/Rge 15-34-12E  
GPS 1473 feet from south section line  
GPS 3748 feet from east section line

35.00

TECHNICIAN'S PLUGGING REPORT

Operator License # 33594  
Operator: QUITO, INC.  
Name & 1613 WEST 6TH ST.  
Address BARTLESVILLE, OK 74003

Lease/Well# DEARMOND # 9 (GPS DEA08)  
County CHAUTAUQUA  
Well Total Depth 992 feet  
Production Pipe: 1.5" Size Feet 936'  
Surface Casing: 6.6250" Size Feet 20'  
SWD Well Input Well X D & A  
Other well as hereinafter indicated: UIC DOCKET # E-16,972

Plugging Contractor: QUITO, INC. Lic. # 33594  
Address: 1613 WEST 6TH ST., BARTLESVILLE, OK 74003

Company to plug at: Hour: \_\_\_\_\_ Day: 29 Month: 11 2006

Plugging proposal received from: TOM BILYEU

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2302

Were: TO PULL OUT 1.5" CEMENT LINED PIPE, THEN RUN RAG PACKER ON 2" PIPE DOWN 5.25" CASING TO TD & CEMENT ANNULUS ON TOP OF PACKER. THEN TO CEMENT DOWN 2" & SQUEEZE OFF WITH PRESSURE.  
TO PLUG BROKE-OUT & LEAKING OLD ABANDONED INJECTION WELL.

Plugging Proposal Received by: RON ROWE

Plugging attended by Agent: All X Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 29 Month: 11 2006

Actual Plugging Report: OPERATORS WELL RECORD OF 1955 HAS THIS WELL EQUIPPED WITH 20' OF 6.6250", 742' OF 5.25", & 936' OF 1.5" CEMENT LINED PIPE.

PULLED 1.5" PIPE OUT. RAG PACKER ON 2" WOULDN'T GO DOWN 5.25" CASING (EVIDENTLY 5.25" IS BAD & ROUGH-WALLED). TRIED TO RUN 1" WORK-STRING INSIDE 5.25" TO BOTTOM, BUT APPARENTLY CASING HAD COLLAPSED, & COULDN'T GET 1" PAST 185'. PERFORATED 5.25" @ 175', 112', & 50' (6 SHOTS TOTAL). RAN 1" WORK-STRING BACK IN TO 300' & PUMPED/CIRCULATED CEMENT TO SURFACE, INSIDE & OUTSIDE 5.25" CASING. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 60 SACKS CEMENT. PLUGGED LEAKING INJECTION WELL.

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

**INVOICED**  
DATE 2-12-08  
INV. NO. 200806196

Signed: RON ROWE  
**RECEIVED**  
FEB 20 2007

RON ROWE  
TECHNICIAN

KCC WICHITA

PR