

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21638-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 21-7S-19W
2310 feet from S Section Line, 2090 feet from E Section Line
Lease Name: SCHNEIDER Well #: 2
County: ROOKS Total Vertical Depth: 3448 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3431	0	235 SX
SURF	8.625	210	0	110 SX <u>112.06</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2008 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ANDREW NOONE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel - 800# hulls - 11 sxs gel spacer. Perf at 1510' and 900'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2008 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Swift Services hooked onto 4 1/2" casing and pumped 40 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pumped 11 sxs gel with 100# hulls.
Pumped 10 sxs cement down the annulus.
Hooked back up to 4 1/2" - pumped 140 sxs cement with 300# hulls.

Perfs:

Top	Bot	Thru	Comments
3346	3353		
3326	3328		

INVOICED
DATE 2-12-08
INV. NO. 2008061187

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 07 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN)

100

PKF


JAN 30 2008

BAIRD OIL COMPANY
 BOX 7
 LOGAN, KS 67646

REPLACEMENT CARD
 #2 SCHNEIDER
 21-7-19W
 400' FNL &
 2240' FEL, SE/4

COUNTY ABERCROMBIE DRILLING, INC., CITY ROOKS

GEOLOGICAL FIELD GROVER WEST



ELV 1988 KB SPD 4/3/82 CARD ISSUED 1/6/83 P 24 BOPD, NW
 1980 GL LKC 3326-3353 OA
 API 15-163-21,638 ARB OH 3431-3448

LOG	Top	Depth/Bottom	8 5/8 " 210/110SX, 4 1/2 " 3431/235SX
ANH	1486 + 502	DST (1) 3291-3326 (LKC) / 30-30-30-30, REC 5' M, SIP 116-96#, FP 58-58 / 58-58#
B/ANH	1520 + 468	DST (2) 3316-44 (LKC) / 45-45-45-45, 70' GIP, REC 35' HOCM (30% OIL, 70% W), 15' FREE OIL (GR 37%), SIP 120-120#, FP 65-65 / 65-65#
TOP	2932- 944	
HEEB	3132-1144	
TDR	3158-1170	DST (3) 3339-64 (LKC) / 45-45-45-45, REC 20' FREE OIL (GR 36%), 30' HOCM (35% OIL, 65% M), SIP 135-96#, FP 48-48 / 48-48#
LANS	3177-1189	
SEV SH	3291-1303	
BKC	3391-1403	DST (4) 3425-48 (ARB) / 45-45-45-45, 315' GIP, REC 630' FREE OIL, 63' HOCM, SIP 947-909#, FP 96-184 / 232-281#
ARB	3426-1438	
LTD	3446-1458	
RTD	3448-1460	

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

CORRECTION & INFO RELEASED: 10/24/85 - ORIGINALLY FIRST REPORTED IN 330' FNL & 550' FWL, SE/4 - ADDED DST'S
 NOTE: INFO RELEASED: 10/25/84 - WAS TIGHT HOLE