

TO  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21766-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 28-7S-19W  
300 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: SCHNEIDER Well #: 4  
County: ROOKS Total Vertical Depth: 3441 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3434	0	235 SX
SURF	8.625	207	0	160 SX

111.83

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2008 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ANDREW NOONE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 4% gel - 800# hulls - 11 sxs gel spacer.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2008 3:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Swift Services hooked onto 4 1/2" casing and pumped 40 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pumped 11 sxs gel with 100# hulls.  
Pumped 10 sxs cement down annulus. S.I.P. 200#.  
Hooked back up to 4 1/2" and pumped 120 sxs cement with 150# hulls.  
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3336	3340		
3316	3322		

**INVOICED**  
DATE 2-12-08  
INV. NO. 200 8061187

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 07 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

HP-

Signed

Pat Bedore

(TECHNICIAN)

pat

REPLACEMENT CARD


BAIRD OIL COMPANY  
BOX 7  
LOGAN, KS 67646

#4 SCHNEIDER

28-7-19W  
300' FNL &  
660' FEL, NW/4

CONTR ABERCROMBIE DRILLING, INC. CTY ROOKS

GEOLOGICAL FIELD GROVER WEST EXT  
(1/4 S)



ELV 1976 K.B. SPD 8/21/82 CARD ISSUED 1/6/83 IP P 24 BO & 24 BWPD  
LKC 3316-3322  
ARB OH 3434-3441

LOG	Top	Depth/Datum	
			API 15-163-21,766
			8 5/8 " 207/160SX; 4 1/2 " 3434/235SX
ANH	.....	1460+ 516	DST (1) 3276-3312 (LKC) / 30-30-30-30, REC 5' OIL SPKD DM, SIP 82-69#, FP 41-41 / 55-55#
B/ ANH	.....	1494+ 482	DST (2) 3306-30 (LKC) / 30-30-30-30, REC 5' OCDM, SIP 69-41#, FP 41-27 / 27-27#
TOP	.....	2922- 946	DST (3) 3325-50 (LKC) / 45-45-45-45, REC 20' OCM, SIP 57-57#, FP 28-28 / 28-28#
HEEB	.....	3123-1147	DST (4) 3343-72 (LKC) / 30-30-30-30, REC 5' OCM, SIP 57-57#, FP 55-55 / 55-55#
TOR	.....	3147-1171	DST (5) 3415-41 (LKC, ARB) / 45-45-45-45, REC 30' FO, 65' HOCDM, SIP 966-911#, FP 55-69 / 82-96#
LANS	.....	3164-1188	MICT - CO, (ARB OH), AC 300G (15% SGA), SWB LD, RE-AC 250G (28%), 1500G (15%) & 6 BBLS OVERFLUSH (3036-3340), SWB LD, RE-AC 1500G (15% SGA) & 12 BBLS OVERFLUSH, SWB DWN, SO, PF (LKC) 3316-22, AC 1750G (28% & 15%) & 6 BBLS OVERFLUSH, SWB LD, SO, POP, P 24 BO & 24 BWPD (GR 31') - COMMINGLED
STARK SH	.....	3281-1305	
BKC	.....	3378-1402	
ARB	.....	3431-1455	
RTD	.....	3441-1465	

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

INFO RELEASED: 4/12/84 - WAS TIGHT HOLE