

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21866-00-00  
Spot: NESENE Sec/Twnshp/Rge: 19-7S-19W  
1650 feet from N Section Line, 330 feet from E Section Line  
Lease Name: SCHOELLER Well #: 4  
County: ROOKS Total Vertical Depth: 3474 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3473	0	250 SX
SURF	8.625	208	0	160 SX

112-91

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2008 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ANDREW NOONE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 295 sxs 60/40 pozmix - 4% gel - 800# hulls - 16 sxs gel spacer. Perf 1550' and 925'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/29/2008 10:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Swift Services hooked onto 5 1/2" casing and pumped 40 sxs 60/40 pozmix - 4% gel with 150# hulls.  
Pumped 16 sxs gel with 550# hulls.  
Pumped 150 sxs cement. S.I.P. 200#.  
Pumped 70 sxs cement down annulus. S.I.P. 100#.  
Topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3394	3396		
3390	3392		
3369	3371		
3349	3351		
3255	3257		

**INVOICED**  
DATE 2-12-08  
INV. NO. 2008001187

RECEIVED  
KANSAS CORPORATION COMMISSION  
**FEB 07 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

Pat Bedore

(TECHNICIAN)

110

*[Handwritten signature]*

BAIRD OIL COMPANY  
BOX 7

LOGAN, KS 67646

CONTR ABERCROMBIE DRILLING

GEOLOGICAL

ELV 2014 KB SPD 11/16/82 CARD ISSUED 2/3/83  
2006 GL

REPLACEMENT CARD


#4 SCHOELLER

CTY ROOKS

FIELD US 24 EXT (1/8 W)

IP P 201 BOPD, TR WTR  
LKC 3349-3396 OA

19-7-19W  
NE SE NE



LOG	Tops	Depth/Datum	
ANH	1517+	497	API 15-163-21,866
B/ANH	1551+	463	8 5/8 " 208/160SX, 5 1/2 " 3473/250SX
TOP	2956-	942	DST (1) 3312-44 (LKC) / 30-45-30-45. REC 2' FO. 4' OCM. SIP 495-124#, FP 31-31 / 41-41#
HEEB	3158-	1144	DST (2) 3337-62 (LKC) / 45-45-45-45. 386' GIP. REC 220' CL GSY OIL. 64' OCM. SIP 892-863#, FP 59-78 / 98-118#
TOR	3182-	1168	DST (3) 3358-80 (LKC) / 45-45-45-45. 478' GIP. REC 376' CL GSY OIL. 122' HOCM. SIP 1019-1009#, FP 68-118 / 167-206#
LANS	3197-	1183	DST (4) 3375-3405 (LKC) / 45-45-45-45. 132' GIP. REC 1' FO. 66' OCM. SIP 1010-877#. FP 31-31 / 41-41#
STARK	3316-	1302	MICT - CO, PF (LKC) 3394-96, 3390-92. AC 250G (28%), SWB LD, SO, RE-AC 1250G (15%) & 6 BBLS OVERFLUSH, SWB LD, SO, PF (LKC) 3369-71, AC 250G (28%), SWB LD, SO, RE-AC 1500G (15%) & 6 BBLS OVERFLUSH, SWB LD, SO, PF (LKC) 3255-57, 3349-51, AC 250G (28%), SWB LD, SO, RE-AC 1500G (15%) & 6 BBLS OVERFLUSH, SWB LD, SO, POP, P 201 BOPD, TR WTR (TR 38%), 12/22/82
BKC	3401-	1387	
RTD&LTD	3474-	1460	

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

INFO RELEASED: 4/5/84 - WAS OIL WELL - TIGHT HOLE