

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: ENHR Docket #: E12,571
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-27-07 (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 4849 Bottom: 4880 T.D. 5215
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-10310-00-01
Lease Name: Wilburton Morrow Sand Unit
Well Number: 1601 W
Spot Location (QQQQ): C-SE-SE
660 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 32 Twp. 34 S. R. 41 East West
County: Morton
Date Well Completed: 9-7-63 spud
Plugging Commenced: 12-10-07
Plugging Completed: 12-10-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1469	—
				4 1/2	4970	954

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Top of junk @ 2738, 20 sx plug on junk, TOC 2650. Ran 2 3/8 t packer to 1516 pres. test 4 1/2 to 300. 4 1/2 was stuck inside 8 5/8 @ 1000. Perf 4 1/2 @ 1420. Squeezed 56 sx cmt. down 4 1/2 and out perf, left TOC in 4 1/2 @ 1200. Shot 4 1/2 base + circ. hole w/mud mixed 40 sx 950 to 830 40sx 400 to 280 10sx 40 to 0 Capped 8 5/8 3 ft below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas Av. PO Box 2528 Liberal, KS 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Kenny Andrews
(Address) 1701 N. Kansas PO Box 2528 Liberal, KS 67905

SUBSCRIBED and SWORN TO before me this 4th day of Feb, 2008
Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 07 2008
CONSERVATION DIVISION
WICHITA, KS