

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 08 2008
Type or Print on this Form
Form must be Signed
All blanks must be Filled
CONSERVATION DIVISION
WICHITA, KS

Form CP-4

December 2003

Lease Operator: Exxon Mobil Oil Corporation
Address: PO Box 4358 Houston TX 77210
Phone: 713 431 1936 Operator License #: 5208

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12-21-07 (Date)

by: Ken Jehlik (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Chase Depth to Top: 2620' Bottom: 2740' T.D. 2920'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129 00357-00-00

Lease Name: H. Ehrhard

Well Number: 1

Spot Location (QQQQ): _____ - _____ - C - NW

3960 Feet from ☐ North / ☒ South Section Line

3960 Feet from ☒ East / ☐ West Section Line

Sec. 28 Twp. 34 S. R. 39 ☐ East ☒ West

County: Morton

Date Well Completed: 1930

Plugging Commenced: 12-31-07

Plugging Completed: 1-8-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13"	600	—
				8 5/8	2549	700
				5 1/2	1605	1275
Schlumberger ran bond log on 13", bond was satisfactory						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8 to 2300. Mixed 400 lb hulls & 50 sx plug @ top of liner from 2538 to 2388. Pulled 5 1/2 & 8 5/8. Ran 2 3/8 to 630. Mixed 25 sx 630 to 595. Tag @ 590. Mixed 50 sx 590 to 530. 25 sx 40 to 0. Used 330 bbls. mud during plugging. Cut off & capped 13" 3 ft below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731


Name of Party Responsible for Plugging Fees: EXXON MOBIL PROD CO

State of KANSAS County, MORTON, ss.

RICHARD B LEWIS

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) RB Lewis

(Address) PO Box 400 HUGOTON KS 67951

SUBSCRIBED and SWORN TO before me this 22 day of January, 2008

Doretta L. Delay
Notary Public

My Commission Expires: 12-27-08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jacqueline Davis 281-654-1913 2/7/08