

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Section plat grid with 4 columns and 4 rows, used for locating the well.

Locate well correctly on above Section Plat

Sedgwick County. Sec. 5 Twp. 26 Rge. 2 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines S/2 SE/4 NW/4
Lease Owner White & Ellis Drilling Co., et al
Lease Name Broers Well No. 1
Office Address Madison, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed August 26 19 50
Application for plugging filed September 13 19 50
Application for plugging approved August 28 19 50
Plugging commenced September 1 19 50
Plugging completed September 1 19 50
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley
Producing formation Depth to top Bottom Total Depth of Well 3030 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

base
Filled hole with rotary mud to top surface pipe. Set 15' rock bridge and cemented with 12 sax cement. Filled hole with rotary mud to top of surface. Bridged with 5' rock and cemented with 5 sax cement. Cap plug.

9-14-50

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to White & Ellis Drilling Company, Madison, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
C. W. Wilson (employee of Contractor)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MORRISON DRILLING COMPANY, INC.

(Signature) BY: P. O. Drawer 712, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13th day of September, 19 50

My commission expires January 10, 1951.

Notary Public.



SE 1/4 NW 1/4 SEC. 5-26-2E

Casing record

8 1/2" 118'
 5 1/2" 3004
 5 1/2" pulled 2724
 W.D. 3030 1/2

Location: ~~SE 1/4 NW 1/4 Sec 5-26-2E~~

Sedgwick County, Kansas

Farm: Broers

Well Owners: White & Ellis, et al.

Contractor: Martin & Cash Drlg. Co.

Start 8-9-50 Completed 8-27-50

Formation

Depth-figures indicate bottom of formation

soil	0-6
clay	25
clay-yellow	35
red rock	40
shale & shells	165
lime & shale	355
red rock	338
lime & shale	590
lime	615
lime & shale	800
shale & lime	1015
lime & shale	1165
sand	1170
shale & lime	1260
shale & shells	1350
shale & lime	1552
lime & shale	1590
shale	1594
sand & shale	1636
shale	1650
lime & shale streaks	1678
shale & lime	1880
lime	1902
shale & lime	1935
lime & shale streaks	2026
lime & shale	2140
shale & lime	2222
broken lime	2232
lime & shale	2362
shale	2376
lime	2424
lime & shale	2470
lime	2498
shale	2540
shale & shells	2580
lime	272 5
slate	2735
shale & lime	2760
lime & shale	2936
shale & shells	2979
lime	2984
shale & conglomerate	2995
shale	2999
lime	3004

Cable tools	
vari-colored shale	3024
red rock	3027 1/2
green sand	3028
chat	3030 1/2

Dry hole-plug and abandon

RECEIVED
 REGISTRATION COMMISSION
 PLUGGER 51950
 FILE SECTION 16 DIVISION
 WICHITA, KANSAS
 BOOK PAGE 16 LINE 16

\$ 3.00 per hour