

15-173-02000-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH


Locate well correctly on above Section Plat

Sedgwick County. Sec. 5 Twp. 26S Rge. 2 (E) (XX)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. 330' from N line 330' from E line  
 Lease Owner Nelson Drilling Company and Sloan & Zook Company  
 Lease Name Broers Well No. 1  
 Office Address 1022 Union National Bank Building - Wichita (2) Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed October 4 19 44  
 Application for plugging filed October 3 19 44  
 Application for plugging approved October 3 19 44  
 Plugging commenced October 3 12 Midnight 19 44  
 Plugging completed ~~12 Midnight October 3~~ 6 A.M. October 4th 19 44  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lilley  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3007 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8"	148'	No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Dumped 2 Ton aqua-jel in pits 2:30 P.M. October 3 - circulated until mud heavy. Pumped 15 sacks cement on bottom, filled hole with heavy mud to 148' Plug bottom of surface pipe with cement to 139'; filled with mud to 10'; plugged top of surface and cellar floor with cement; Filled cellar with dirt.

**PLUGGING**  
 FILE  
 5 26 22 E  
 134 NE-18

STATE CORPORATION COMMISSION  
 OCT 6 - 44  
 10-6-44

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to Nelson Drilling Company  
 Address 1022 Union National Bank Building - Wichita, Kansas (2)

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

A.H. Parks (employee or owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A.H. Parks  
1022 Union National Bank Bldg. Wichita, Mo.  
 (Address)

SUBSCRIBED AND SWORN to before me this 4th day of October 19 44

My commission expires Dec. 4, 1944  
Maxwell Wright Notary Public.

COMPANY: Nelson Drilling Company & Sloan & Zook  
 CONTRACTOR: Nelson Drilling Company  
 FARM: Broers #1  
 LOCATION: NE SW SE - Section 5-26S-2E  
 Sedgwick County, Kansas.  
 COMMENCED: September 23, 1944  
 COMPLETED: October 4th, 1944

0	to	145	Surface
145	to	250	Shale
250	to	425	Shale and Shells
425	to	475	Lime
475	to	525	Lime
525	to	580	Sandy Lime
580	to	620	Shale
620	to	640	Sand
640	to	725	Sand
725	to	1025	Sand and Shale
1025	to	1385	Shale and Lime Shells
1385	to	1660	Shale and Shells
1660	to	1780	Shale and Shells
1780	to	1890	Lime
1890	to	2005	Lime
2005	to	2180	Shale
2180	to	2385	Sandy Lime
2385	to	2490	Lime
2490	to	2512	Lime - Top Lansing
2512	to	2625	Lime
2625	to	2635	Shale
2635	to	2860	Lime
2860	to	2865	Shale
2865	to	2880	Lime
2880	to	2890	Shale
2890	to	2895	Lime
2895	to	2940	Shale
2940	to	2945	Lime
2945	to	2961	Shale - variegated
2961	to	2963	Coarse Sand
2963	to	2971	Variegated Shale
2971	to	2974	Coarse Sand
2974	to	3004	White Chert ( Top Mississippi)
		3007	Total Depth

DRILLING  
 FILE  
 BOO: 5 26 2 E  
 134 18

Set 149 feet of 8 inch surface pipe. Cemented with 80 sax of cement.

DRY, ABANDONED AND PLUGGED

TOPS

Lansing 2512'  
 Mississippi 2974'

C E R T I F I C A T E

I, A.H. Parks, do hereby certify that the above and foregoing is a true and correct copy of log of the Broers #1, Section 5-26S-2E, Sedgwick County, Kansas, as reflected by files of the C.C. Nelson Drilling Company.

*A.H. Parks*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 4th day of October, 1944.

*Mycom. expires 12/4/44*

*Stepwell Wright*