


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

SEDGWICK County. Sec. 6 Twp. 26 Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines 100' S. OF CENTER W 1/2 NW 1/4

Lease Owner GLEN DRILLING INC. NE 1/4

Lease Name TIMMERKAMP Well No. 1

Office Address Box 547

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 10-8 19 57

Application for plugging filed 10-8 19 57

Application for plugging approved 10-8 19 57

Plugging commenced 10-8 19 57

Plugging completed 10-8 19 57

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUAL DURKEY

Producing formation NONE Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3025 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	110'	8 5/8	110'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

CIR. HEAVY MUD FROM BOTTOM TO TOP OF HOLE-PULLED OUT DRILL PIPE SET BRIDGE @ 140' SPOTTED 15 SACKS OF CEMENT THRU DRILL PIPE-FILLED HOLE WITH MUD UP TO 15' & MIXED 5 SACKS OF CEMENT & FILLED UP TO TOP CUT OFF SURFACE BELOW PLOW DEPTH.

RECEIVED  
STATE CORPORATION COMMISSION  
10-17-57  
OCT 17 1957  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLEN DRILLING, INC.

Address Box 547 EL DORADO, KANSAS

STATE OF KANSAS, COUNTY OF BUTLER, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen Gaines

Box 547 EL DORADO, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 14TH day of OCTOBER, 19 57

My commission expires JUNE 21, 1961

Notary Public.

PLUGGING  
FILE SEC 6 T 26 2E  
BOOK PAGE 52 LINE 42

WELL LOG

COMPANY

GLEN DRILLING, INC.  
Box 547  
EL DORADO, KANSAS

LOCATION:  
100' SOUTH OF CENTER  
W $\frac{1}{2}$ -NW $\frac{1}{2}$  NE $\frac{1}{4}$   
SEC 6-26-2E  
SEDGWICK COUNTY, KANSAS

CONTRACTOR

GLEN DRILLING, INC.  
Box 547  
EL DORADO, KANSAS

COMM:

OCTOBER 3, 1957

COMP:

OCTOBER 8, 1957

FARM:

TIMMERKAMP # 1

TOTAL DEPTH 3026-ROTARY 110' OF 8 5/8" SURFACE PIPE-CEMENTED

FROM	TO	
0	3	SOD
3	7	GRAVEL
7	100	SHALE
100	110	BROKEN LIME
110	195	SHALE & SHELLS
195	395	LIME
395	785	LIME & SHALE STREAKS
785	870	LIME & SHALE
870	1115	SHALE & SHELLS
1115	1580	SHALE & LIME STREAKS
1580	1650	SHALE SANDY
1650	1905	LIME & SHALE
1905	1945	LIME
1945	2035	SHALE & LIME
2035	2255	SHALE & LIME STREAKS
2255	2370	SHALE & LIME
2370	2445	LIME
2445	2535	LIME & SHALE
2535	2563	LIME K. C.
2563	2656	LIME
2656	2705	LIME BLACK K. C.
2705	2859	SHALE & LIME
2859	2939	LIME & SHALE
2939	2985	SHALE & LIME
2985	3015	SAND & SHALE
3015	3024	LIME MISS
3024	3026	CHERT HARD
	3026	TOTAL DEPTH

I HEREBY CERTIFY THAT THE FOREGOING IS A TRUE AND CORRECT COPY OF THE WELL LOG FOR THE TIMMERKAMP WELL # 1 DRILLED FOR THE GLEN DRILLING, INC. AND COMPLETED OCTOBER 8, 1957.

GLEN DRILLING, INC.  
*Glen Gaines*  
GLEN GAINES, PRESIDENT

STATE OF KANSAS ) SS  
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO BEFORE THE UNDERSIGNED, A NOTARY PUBLIC IN AND FOR COUNTY AND STATE AFORESAID THE 15TH DAY OF OCTOBER, 1957.

*Alona M. Wentworth*  
ALONA M. WENTWORTH NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 21, 1961.

FILED  
FILE SEC 6 P 26 2E  
BOOK PAGE 52 LINE 42

WELL LOG

COMPANY GLEN DRILLING, INC.  
Box 547  
EL DORADO, KANSAS

LOCATION:  
100' SOUTH OF CENTER  
W 1/2 - NW 1/2 NE 1/2  
SEC 6-26-2E  
SEDGWICK COUNTY, KANSAS

CONTRACTOR GLEN DRILLING, INC.  
Box 547  
EL DORADO, KANSAS

COMM: OCTOBER 3, 1957

COMP: OCTOBER 8, 1957

FARM: TIMMERKAMP # 1

TOTAL DEPTH 3026-ROTARY 110' OF 8 5/8" SURFACE PIPE-CEMENTED

FROM	TO	
0	3	SOD
3	7	GRAVEL
7	100	SHALE
100	110	BROKEN LIME
110	195	SHALE & SHELLS
195	395	LIME
395	785	LIME & SHALE STREAKS
785	870	LIME & SHALE
870	1115	SHALE & SHELLS
1115	1580	SHALE & LIME STREAKS
1580	1650	SHALE SANDY
1650	1905	LIME & SHALE
1905	1945	LIME
1945	2035	SHALE & LIME
2035	2255	SHALE & LIME STREAKS
2255	2370	SHALE & LIME
2370	2445	LIME
2445	2535	LIME & SHALE
2535	2563	LIME K.C.
2563	2656	LIME
2656	2705	LIME BLACK K.C.
2705	2859	SHALE & LIME
2859	2939	LIME & SHALE
2939	2985	SHALE & LIME
2985	3015	SAND & SHALE
3015	3024	LIME MISS
3024	3026	CHERT HARD
	3026	TOTAL DEPTH

I HEREBY CERTIFY THAT THE FOREGOING IS A TRUE AND CORRECT COPY OF THE WELL LOG FOR THE TIMMERKAMP WELL # 1 DRILLED FOR THE GLEN DRILLING, INC. AND COMPLETED OCTOBER 8, 1957.

GLEN DRILLING, INC.  
*Allen Gaines*  
GLEN GAINES, PRESIDENT

STATE OF KANSAS ) SS  
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO BEFORE THE UNDERSIGNED, A NOTARY PUBLIC IN AND FOR COUNTY AND STATE AFORESAID THE 15TH DAY OF OCTOBER, 1957.

*Alona M. Wentworth*  
ALONA M. WENTWORTH NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 21, 1961.

STATE OF KANSAS

OCT 17 1957

CONSERVATION DISTRICT  
Wichita, Kansas

PLUGGING  
FILE SEC 6 T 26 R 2E  
BOOK PAGE 52 LINE 42