

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 11921057000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Quinque Operating Company KCC License #: 5225
(Owner / Company Name) (Operator's)

Address: 908 N.W. 71st St. City: Oklahoma City

State: OK Zip Code: 73116 Contact Phone: (405) 840 - 9876

Lease: Crooked L Well #: 1-21A Sec. 21 Twp. 32 S. R. 28 East West

QSW - W12 NW SW14 Spot Location / QQQQ County: Meade

1440 1429 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4912 5102 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # 02-CONS-294-GREG ENHR Docket # E28094.1 Other: _____

Conductor Casing Size: 20" Set at: 60' Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 1066' Cemented with: 675 Sacks

Production Casing Size: 4 1/2" Set at: 5091' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4834'-4838'

Elevation: 2470' (G.L. / K.B.) T.D.: 5200' PBTD: 5035' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

**RECEIVED
KANSAS CORPORATION COMMISSION**

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

See attached plugging procedure.

JAN 28 2008

**CONSERVATION DIVISION
WICHITA, KS**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Blaine Flaming, Field Supervisor

Quinque Operating Company Phone: (806) 202 - 0046

Address: 908 N.W. 71st St., Oklahoma City, OK 73116 City / State: Oklahoma City, OK

Plugging Contractor: Dollar Oilfield Services KCC License #: 33311

Address: P.O. Box 744, Perryton, TX 79070 Phone: (806) 435 - 3373
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 3/1/08 (approx.)

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/24/2008 Authorized Operator / Agent: Catherine Smith
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

QUINQUE OPERATING COMPANY
908 N.W. 71st ST.
OKLAHOMA CITY, OK 73116
(405) 840-9876 (OFFICE) (405) 840-2011 (FAX)

CROOKED L #1-21A SWD
Sec 21-32S 28W
Meade Co., KS

PLUGGING PROCEDURE:

1. MIRU WOCU. NU BOP.
2. Release R4 Tension Pkr that is set at 4810'. POOH.
3. PU & RIH with tubing. Set CIBP at 4800'. Circulate 10 sx cement on top of plug.
4. PUH w/tubing to 4600'. Circulate hole and pump 25 sx cement.
5. PUH w/tubing to 2500'. Circulate hole and pump 25 sx cement.
6. PUH w/tubing to 1150'. Circulate hole and pump 20 sx cement.
7. PUH w/tubing to 450'. Circulate hole and pump 35 sx cement.
8. PUH w/tubing to 70'. Circulate hole and cement to surface w/25 sx cement.
9. ND BOP. Remove WH. Place marker over casing noting well name. Place dry hole marker per instructions.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2008
CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

QUINQUE OPERATING COMPANY
908 NW 71ST ST
OKLAHOMA CITY, OK 73116-7402

February 12, 2008

Re: CROOKED L #1-21A
API 15-119-21057-00-01
21-32S-28W, 1429 FSL 5102 FEL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 10, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888